

SCT College of Engineering, Trivandrum

TENDER SCHEDULE

Name of work: - *SCT College of Engineering, Trivandrum - Providing leak Proofing work to the Roof of Students Union Room near Electronics Lab*

Sl No.	Qty	Specifications	Unit	Rates(Rs)	Amount(Rs)
1.	2 No	Cutting down the branches of trees touching the roof including cleaning the roof of the building etc.complete.	Each		
2.	105 M ²	Chipping and removing old and damaged cement plaster including disposal of un serviceable materials within 50m of lead as per the direction of Engineer-in-charge.	M ²		
3.	105 M ²	Grouting with cement grout 22kg/10m ² including water proofing compound 200ml/50kg of cement.	M ²		
4.	5.50 M ³	Providing cement concrete 1:1 ^{1/2} :3 using aggregate varying from 6mm-20mm including cost and conveyance of materials labour charges etc.complete.	M ³		
5.	105 M ²	Plastering with cement mortar 1:3, 9mm thick mixing with D fixit (for leak proofing) including all cost and conveyance etc.complete.	M ²		
6.	110 M ²	Painting with synthetic enamel paint of approved quality including cost and conveyance of materials, labour charges etc.complete.	M ²		
7.	4.00 M	Providing and fixing 100mm dia PVC pipe for draining out water.	M		
8.	1 No	Providing and fixing 100mm dia PVC pipe bend including cost and conveyance of materials etc.complete.	Each		
		Total			

I agree to undertake to execute the above work at an amount of Rs.....as

above on item rate basis

Dated Signature

Name & address of the contractor

PRINCIPAL