

**SCT College of Engineering, Trivandrum**

**TENDER SCHEDULE**

**Name of work: - SCT College of Engineering, Trivandrum - Providing and Laying of Interlocking Tiles in the passage from the Generator station to Biotechnology Lab**

Sl No.	Qty	Specifications	Unit	Rates(Rs)	Amount(Rs)
1.	180.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30m measured at a height of 1m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared.	M <sup>2</sup>		
2.	176.00	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction of approved size, design and shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc.all complete as per the direction of Engineer-in-charge	M <sup>2</sup>		
3.	0.50	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level C.C 1:2:4(1 Cement: 2 Sand(zone w ) : 4 graded stone aggregate 20mm nominal size etc.)	M <sup>3</sup>		
4.		<b>TOTAL</b>			

I agree to undertake to execute the above work at an amount of Rs.....as

above on item rate basis

Dated Signature

Name & address of the contractor

**PRINCIPAL**