

SCT College of Engineering, Trivandrum

TENDER SCHEDULE

Name of work: - *SCT College of Engineering, Trivandrum – Providing an Emergency Exit Door to CAD Lab in M.E Department*

Sl No.	Qty	Specifications	Unit	Rates(Rs)	Amount(Rs)
1.	1 m ³	Demolishing brick work manually / mechanical means including stacking of serviceable material and disposal of unserviceable material certain 50 m lead as per the direction of Engineer-in-charge.	M ³		
2.	1 No	Dismantling door, windows and clerestory windows (steel or wood) shutter including chow chats, architrave, and holdfasts etc.complete and stacking within 50m lead.	Each		
3.	0.50m ³	Providing wood work in frame of doors, windows and clerestory windows and other frames wrought framed and fixed in position with holdfast hinges or with dash fastener of required dia and length (holdfast larger/dash fastener shall be period for separately) hiring good quality Anjili wood/Jack wood.	M ³		
4.	2.50m ²	Providing and fixing panelled or panelled glazed shutters for doors, windows and clerestory windows, 35mm thick shutters, including ISI marked M.S pressed butt hinger bright finished of	M ²		

		required size with necessary screws excluding paneling within will be paid for separately all complete as per the direction of Engineer-in-charge hiring Anjili wood/Jack wood.			
5.	2.00 m ²	Plastering with C.M 1:4,12mm thick are coat floated level and trowelled smooth watering, curing etc.complete.	M ²		
6.	2.00 m ²	Painting the walls and ceiling with plastic emulsion paint of approved brand and manufacture one or more coats to given are even shade after cleaning the surface as directed by the Engineer-in-charge.	M ²		
7.	2.50 m ²	Painting the doors, windows etc.with synthetic enamel paint of approved brand and manufacture on new surface one or more coats to give an even shade after sand papering and cleaning the surface as directed by the Engineer-in-charge.	M ²		
		TOTAL			

I agree to undertake to execute the above work at an amount of Rs.....as above on item rate basis.

Dated Signature

Name & Address of the contractor

PRINCIPAL